

PROJ #2021027003	ADDENDUM #1	DATE: 01/10/2025
------------------	-------------	------------------

NOTICE: This Addendum No. 1, issued in accordance with the Contract Documents, is incorporated into the Contract Documents and supersedes and updates all conflicting information and is hereby amended in certain particulars as follows:

CHANGES TO THE CONTRACT DOCUMENTS:

1. CHANGES TO CONTRACT TIMES:

- a. Location No. 1 (Benzie St. and Crystal Ave. Storm Chambers and Structures)
The contractor may work on this item starting from the notice to proceed and be completed by November 30, 2025. Once work has started on this item, it shall be completed in a timely manner. The contractor shall complete the work in a manner that will allow continued traffic along Crystal Avenue, a minimum of one-way traffic during work activities and two-way traffic during non-working periods. All excavation holes shall be protected in a safe manner. The contractor should try to avoid work for a week before a holiday or special event and shall restore the Betsie Valley Trail in a timely manner.
- b. Location No. 2 (Prospect Street and Crystal Avenue – Village Park)
The contractor may work on this item starting from the notice to proceed and be substantially completed by June 27, 2025. If that is not possible, the contractor may start work after Labor Day and be completed by November 30, 2025. The contractor shall complete the work in a manner that will allow continued traffic along Crystal Avenue and Prospect Street, a minimum of one-way traffic during work activities and two-way traffic during non-working periods. All excavation holes shall be protected in a safe manner. The contractor should avoid work around holidays or special events and shall restore the Betsie Valley Trail in a timely manner.
- c. Location No. 3 (2nd Street Rain Garden)
The contractor may work on this item starting from the notice to proceed and be completed by November 30, 2025.
- d. Location No. 4 (Lake Street and Benzie Boulevard Inlet Infiltration Systems)
The contractor may work on this item starting from the notice to proceed and be completed by November 30, 2025.

2. Soil Erosion Sedimentation Control Permit Issued 01/10/2025. Attached

CHANGES TO THE CONTRACT PLANS:

1. None.

END SECTION

DISTRIBUTION: (via email)

All Plan Holders
File

SOIL EROSION, SEDIMENTATION AND STORMWATER CONTROL PERMIT

Permit No: PS25-0001

BENZIE COUNTY ZONING DEPARTMENT
 BENZIE COUNTY GOVERNMENT CENTER
 448 COURT PLACE, P.O. BOX 377
 BEULAH, MI 49617
 (231) 882-9674

FEE PAID: \$240.00
 DATE: 01/10/25
 EXPIRATION DATE: 01/10/26
 BY: _____

(Soil Erosion Control Officer)

ISSUED UNDER THE AUTHORITY OF, PART 91, SOIL EROSION AND SEDIMENTATION CONTROL, OF THE NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION ACT, 1994 PA 451, AS AMENDED, AUTHORITY IS HEREBY GRANTED TO:

1. OWNER

2. APPLICANT

NAME: VILLAGE OF BEULAH	NAME: VILLAGE OF BEULAH
ADDRESS: PO BOX 326	PHONE:
CITY: BEULAH STATE: MI ZIP: 49617	ADDRESS: PO BOX 326
	CITY: BEULAH STATE: MI ZIP: 49617

3. RESPONSIBLE PARTY

NAME:	
PHONE:	_____
ADDRESS:	
CITY:	STATE: ZIP:

4. LOCATION OF PROJECT

STREET & NUMBER: 319 LAKE STREET	PARCEL # 02-506-140-00
BETWEEN: Calc_LOCATION	TOWNSHIP Benzonia
CITY/VILLAGE	Calc_SECTION
SUBDIVISION	LOT(s) BLOCK ZONING DISTRICT

5. DESCRIPTION OF EARTH CHANGE PROJECT:

NPS EGLE grant project consist of installing stormwater chambers, constructing a rai garden and installing catch basin filtration systems in ex. inlets.
 0.7 acres of change
 within 100 ft of Crystal Lake
 April 2025 to November 2025

6. SPECIAL CONDITIONS

--

This instrument does not convey property rights in either real estate or material, nor does it authorize any injury to private property of invasion of public or private rights, nor does it waive the necessity of seeking federal assent, all other permits or complying with other applicable state statutes. This permit shall be posed at the site of work and available for inspection at all times during the duration of the project or until its date of expiration. All work shall be completed in accordance with the plans and specifications submitted and attached hereto. The Erosion Control Officer shall be notified and shall approve of any modifications to the permitted work prior to the start of such work. This permit does not prejudice or limit the right of a land owner to institute proceedings in any circuit court of this state against any person when necessary to protect his rights. Work specified herein shall be initiated and completed not later than the date of expiration.

ADDITIONAL CONDITIONS ON REVERSE

GENERAL CONDITIONS:

In accordance with Rule 1709 promulgated under the authority of Part 91, Soil Erosion and Sedimentation Control, of the Natural Resources and Environmental Protection Act, 1994 PA 45, as amended, and in addition to the information on the attached plan(s) and special conditions, the following general conditions apply to the earth change authorized by this permit:

- 1. Design, construct and complete the earth change in a manner that limits the exposed area of disturbed land for the shortest period of time.**
- 2. Remove sediment caused by accelerated soil erosion from runoff water before it leaves the site of the earth change.**
- 3. Temporary or permanent control measures shall be designed and installed to convey water around, through, or from the earth change at a non-erosive velocity.**
- 4. Install temporary soil erosion and sedimentation control measures before or upon commencement of the earth change activity and maintain the measures on a daily basis. Remove temporary soil erosion and sedimentation control measures after permanent soil erosion measures are in place and the area is stabilized. ("Stabilized" means the establishment of vegetation or the proper placement, grading, or covering of soil to ensure its resistive to soil erosion, sliding, or other earth movement.)**
- 5. Complete permanent soil erosion control measures for the earth change within five calendar days after final grading or upon completion of the final earth change. If it is not possible to permanently stabilize the earth change, then maintain temporary soil erosion and sedimentation control measures until permanent soil erosion control measures are in place and the area is stabilized.**